

7 B.S.

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER AD-A091133	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report Keuka Lake Outlet Dam Oswego River Basin, Yates County, NY Inventory No. 390		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) George Koch		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS New York Department of Environmental Conservation 50 Wolf Road Albany, NY 12233		8. CONTRACT OR GRANT NUMBER(s) DACW-51-79-C-0001
11. CONTROLLING OFFICE NAME AND ADDRESS New York State Department of Environmental Conservation 50 Wolf Road Albany, NY 12233		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		12. REPORT DATE 16 September 1980
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited.		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Keuka Lake Yates County Oswego River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property.		

Original contains color plates: All DTIC reproductions will be in black and white

NOV 5 1980

THIS DOCUMENT IS BEST QUALITY PRACTICABLE. THE COPY FURNISHED TO DDC CONTAINED A SIGNIFICANT NUMBER OF PAGES WHICH DO NOT REPRODUCE LEGIBLY.

AD A091133

DDC FILE COPY

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

393970

**Best
Available
Copy**

Several deficiencies were noted and these should be corrected within 6 months of the date of the final approval of this report. Among the other actions which should be taken are repairing concrete on the post supporting the northern slide gate, filling the small scoured areas behind the sheet pile wall and monitoring the leakage through the masonry wall. In addition, a detailed emergency operation-action plan and warning system should be developed.

The spillways do not have sufficient capacity to discharge the peak outflow from one-half the Probable Maximum Flood (PMF). For this storm event and lesser events, high discharges will cause damage in the channel downstream of the dam. However, dam failure would not significantly increase the hazard to loss of life downstream from that which would exist just prior to an overtopping-induced failure. Therefore, the spillway is assessed as inadequate.


Access	<input checked="" type="checkbox"/>
NTIS	<input type="checkbox"/>
DTIC	
Uncl	
Ju	
By	
District	
Avail	
Dist	
Codes	
1	
A-23	
4	

OSWEGO RIVER BASIN

KEUKA LAKE OUTLET DAM

**. YATES COUNTY, NEW YORK
INVENTORY NO. N.Y. 390**

**PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**



NEW YORK DISTRICT CORPS OF ENGINEERS

AUGUST 1980

**APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED
CONTRACT NO. DACW-51-79-C0001**

80 10 29 008

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

11 16 Sep 84

12 107

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
KEUKA LAKE OUTLET DAM (Inventory, New York)
ID# NO. NY 3907
OSWEGO RIVER BASIN
YATES COUNTY, NEW YORK

Phase I Inspection Report

TABLE OF CONTENTS

PAGE NO.

-	ASSESSMENT	-
-	OVERVIEW PHOTOGRAPH	-
1	PROJECT INFORMATION	1
1.1	GENERAL	1
1.2	DESCRIPTION OF PROJECT	1
1.3	PERTINENT DATA	1
2	ENGINEERING DATA	4
2.1	GEOTECHNICAL DATA	4
2.2	DESIGN RECORDS	4
2.3	CONSTRUCTION RECORDS	4
2.4	EVALUATION OF DATA	4
3	VISUAL INSPECTION	5
3.1	FINDINGS	5
3.2	EVALUATION OF OBSERVATIONS	6
4	OPERATION AND MAINTENANCE PROCEDURES	7
4.1	PROCEDURE	7
4.2	MAINTENANCE OF DAM	7
4.3	WARNING SYSTEM IN EFFECT	7
4.4	EVALUATION	7

34E974

JP

	<u>PAGE NO.</u>
5 HYDROLOGIC/HYDRAULIC	8
5.1 DRAINAGE AREA CHARACTERISTICS	8
5.2 ANALYSIS CRITERIA	8
5.3 SPILLWAY CAPACITY	8
5.4 RESERVOIR CAPACITY	9
5.5 FLOODS OF RECORD	9
5.6 OVERTOPPING POTENTIAL	9
5.7 EVALUATION	10
6 STRUCTURAL STABILITY	11
6.1 EVALUATION OF STRUCTURAL STABILITY	11
7 ASSESSMENT/RECOMMENDATIONS	12
7.1 ASSESSMENT	12
7.2 RECOMMENDED MEASURES	12

APPENDIX

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
- D. REFERENCES
- E. DRAWINGS

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM


Name of Dam: Kewka Lake Outlet Dam (I.D. No. NY 390)
State Located: New York
County Located: Yates
Watershed: Oswego River Basin
Date of inspection: May 8, 1980

ASSESSMENT

Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property.


Several deficiencies were noted and these should be corrected within 6 months of the date of the final approval of this report. Among the other actions which should be taken are repairing concrete on the post supporting the northern slide gate, filling the small scoured areas behind the sheet pile wall and monitoring the leakage through the masonry wall. In addition, a detailed emergency operation-action plan and warning system should be developed.

The spillways do not have sufficient capacity to discharge the peak outflow from one-half the Probable Maximum Flood (PMF). For this storm event and lesser events, high discharges will cause damage in the channel downstream of the dam. However, dam failure would not significantly increase the hazard to loss of life downstream from that which would exist just prior to an overtopping-induced failure. Therefore, the spillway is assessed as inadequate.




George Koch
Chief, Dam Safety Section
New York State Department
of Environmental Conservation
NY License No. 45937

Approved By:


Col. W. H. Smith Jr.
New York District Engineer

Date:





OVERVIEW
KEUKA LAKE OUTLET DAM
I.D. NO. NY 390

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
KEUKA LAKE OUTLET DAM
I.D. NO. NY 390
#53B-613
OSWEGO RIVER BASIN
YATES COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing condition of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam

The Keuka Lake Outlet Dam is a concrete, masonry and earth structure with gated spillways at either end of the structure and an auxiliary spillway in the center.

The dam is approximately 100 feet long and a maximum of 10.5 feet high. At the south end of the structure there are two Rodney Hunt sluice gates 54 inches by 54 inches. The invert of the orifice for these gates is low enough to permit them to be used to partially drain the reservoir. The control mechanism for these gates is located on the top of the dam. Steel sheet pile walls form the entrance channel to this spillway. There is a vertical slide gate controlling flow through an opening which is 4 feet wide by 5.4 feet high on the northern end of the dam. This gate is referred to on the plans as the Birkett Gate. In the center of the dam there is an auxiliary spillway which is 50.8 feet wide. This spillway consists of an earth fill on the upstream slope and a vertical masonry wall with a concrete cap forming the crest.

b. Location

The dam is located in the Village of Penn Yan on the Keuka Lake Outlet. New York State Route 14A (which is also Main Street in the village) is immediately downstream of the dam.

c. Size Classification

The dam is 10.5 feet high and has a maximum storage capacity of 200,750 acre-feet. Therefore, the dam is in the large size category as defined by the "Recommended Guidelines for Safety Inspection of Dams."

d. Hazard Classification

The dam is classified as a "high" hazard structure, due to the presence of 6 homes, a sewage treatment plant, an industrial plant and several local roads located downstream of the dam.

e. Ownership

The dam is owned by the Village of Penn Yan. Mr. Wesley Ryder is the Utilities Manager for the village. He may be contacted at the village offices at 2 Maiden Lane, Penn Yan. The phone number for the offices is (315)536-3374.

f. Purpose of Dam

The dam is used to regulate the level of Keuka Lake. The gates are operated in a manner to provide some flood control regulation.

g. Design and Construction History

Records indicate that this dam was constructed in or about 1880 by the State for use as a canal lock. In 1900, it was renovated and converted to a power dam. New York State Electric and Gas Corporation controlled the dam until 1962, when it was turned over to the Village. The gates on the south end of the dam, were replaced in 1966. Owen C. Hoban, consulting engineer, designed the reconstruction of this portion of the dam. At that time, the two Rodney Hunt Gates currently in existence were installed.

h. Normal Operational Procedures

The water surface in Keuka Lake is maintained according to an established plan. The graph which details the suggested lake level for each month of the year has been included in Appendix C. The water level is changed through the operation of the two Rodney Hunt Gates at the southern end of the dam. The Village of Penn Yan is responsible for the operation of the gates.

1.3 PERTINENT DATA

a. Drainage Area

(square miles) 182

b. Discharge at Dam

STAGE	RODNEY HUNT (GATES-2)*	COMPUTED DISCHARGE (cfs)		TOTAL
		BIRKETT GATE*	CENTER MASONRY SPILLWAY	
708.43	-			-
709	10.8	-		10.8
714	328	12.4		452
716.04	524	193	-	717
718.75	646	227	715	1588

* Gates Fully Open

c. Elevations (USGS Datum)

Top of Dam	718.75
Auxiliary Spillway Crest	716.04
Normal Pool	712-714
Sill of Birkett (Northern) Gate	709.0
Sill of Rodney Hunt (Southern) Gate	708.43

d. Reservoir-Surface Area (sq. miles)

Normal Pool	18.3
-------------	------

e. Storage Capacity (Acre-Feet)

Top-of-Dam	200,750
Auxiliary Spillway Crest	166,000
Sill of Birkett Gate	86,500
Sill of Rodney Hunt Gate	80,500

f. Dam

Type: Earth fill upstream slope, masonry and concrete dam

Dam length(ft):	100
Crest Width(ft):	5

g. Service Spillways

Northern End-Birkett Gate

Type: Single slide gate with an opening 4 feet wide by 5.4 feet high

Invert Elev.	709.0
--------------	-------

Southern End - Twin Gates

Type: Two Rodney Hunt gates; each opening 4.5 feet by 4.5 feet
Control mechanism located above gates.

Invert Elev.	708.43
--------------	--------

h. Auxiliary Spillway

Weir in center of dam with earth fill on upstream slope and vertical masonry wall with concrete cap forming crest.

Length(ft):	50.8
-------------	------

SECTION 2: ENGINEERING DATA

2.1 GEOTECHNICAL DATA

a. Geology

The Keuka Lake Outlet Dam is located in the glaciated Alleghany plateau physiographic province of New York State. The rock in this area consists of limestones, dolomites, shales and sandstones from the Devonian era. The rock lies almost horizontal although there is some sagging in the middle of the Finger Lakes district. Severe trenching or dissection by streams and glacial erosion has carved the upland into very rugged terrain. A review of the "Brittle Structures Map of the State of New York" indicated that there are no faults in the immediate vicinity of the dam.

The surficial soils are the result of glaciations during the Cenozoic Era, the last of which was the Wisconsin glaciation.

b. Subsurface Investigations

No records of any subsurface investigations made in the vicinity of this structure could be located.

2.2 DESIGN RECORDS

No records concerning the original design of this dam were available. Plans prepared in 1955 by Owen C. Hoban, consulting engineer, for the reconstruction of the southern end of the dam and the installation of the Rodney Hunt gates were available. Copies of these plans have been included in Appendix E.

2.3 CONSTRUCTION RECORDS

There were no construction records available.

2.4 EVALUATION OF DATA

The data presented in this report was obtained from the Department of Environmental Conservation files, from Wesley Ryder, utilities manager for the Village of Penn Yan, and from measurements made during the site inspection. While the data available concerning the central and northern end of the dam was somewhat limited, overall the information appeared to be adequate and reliable for Phase I inspection purposes.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspection of the Keuka Lake Outlet Dam was conducted on May 8, 1980. The weather was overcast and the temperature was around 50 degrees. At the time of the inspection, the lake level was at elevation 714.

b. Dam

No serious deficiencies were noted on this structure. The embankment portion forming the upstream slope was in satisfactory condition. The masonry and concrete wall which formed the crest of the auxiliary spillway was also in satisfactory condition. An inspection report from 1977 (a copy of which has been included in Appendix D) indicated that there was a small amount of leakage exiting from the base of the masonry wall. This area could not be observed at the time of this inspection due to the tailwater level. Mr. Ryder, the village Utilities Manager, indicated that this leakage has been occurring for a number of years, with no noticeable increase in quantity.

c. Service Spillways

The two Rodney Hunt gates on the southern end of the dam had been greased recently and were operable. At the time of the inspection, the gates were opened and there was some debris caught in the opening. There was some scour behind the ends of the sheet pile walls on either side of the southern spillway channel.

The slide gate on the northern end was very old but appeared to be operational. The gate control mechanism was supported on four concrete posts at its corners. The concrete on the left front post was deteriorated and partially removed. Further loss of concrete on this post could result in the gate becoming inoperable. The northern bank of the approach channel to this spillway is lined with gabions and riprap. This bank appeared to be in satisfactory condition.

d. Auxiliary Spillway

The auxiliary spillway is formed by the center portion of the dam. It appeared to be in satisfactory condition.

e. Reservoir

There were no indications of soil or channel instability in the immediate vicinity of the dam. The channel which leads from the end of the lake to the dam is relatively narrow and its capacity is further limited by a railroad bridge located approximately 500 feet upstream of the dam. This bridge traps a substantial amount of debris before it reaches the dam. Some trees and brush line the channel banks in the area between this railroad bridge and the dam. These banks should be cleared to reduce the amount of debris which flows to the dam.

f. Downstream Channel

The Main Street Bridge is located immediately downstream of the dam. Beyond the bridge, there are several mill buildings which are located at the edge of the channel.

3.2 EVALUATION OF OBSERVATIONS

Visual inspection revealed several deficiencies on this structure. The following items were noted:

1. Deterioration and partial removal of concrete on post supporting northern slide gate control mechanism.
2. Minor scour behind the sheet pile walls on either side of the southern spillway channel.
3. Debris accumulated in the vicinity of the northern spillway gates.
4. Trees and brush lining the channel upstream of the dam.
5. A small amount of leakage from the base of the masonry wall (observed during a 1977 inspection).

SECTION 4: OPERATION AND MAINTENANCE PROCEDURE

4.1 PROCEDURES

The water surface in this lake is maintained according to the plan which has been included in Appendix C. The water level is controlled by the operation of the two Rodney Hunt gates. A minimum outflow of approximately 20 cfs is maintained to provide flow in the downstream channel. To permit this minimum flow, the gates are kept open about 6 inches.

4.2 MAINTENANCE OF DAM

Routine maintenance of the dam is performed by the Village of Penn Yan.

4.3 WARNING SYSTEM IN EFFECT

No apparent warning system is present.

4.4 EVALUATION

The operation and maintenance procedures for this dam appear to be satisfactory. A detailed emergency operation action plan and warning system should be developed.

SECTION 5: HYDROLOGIC/HYDRAULIC

5.1 DRAINAGE AREA CHARACTERISTICS

The delineation of the contributing watershed to this dam is shown on the map titled "Drainage Area Map - Keuka Lake Outlet Dam" (Appendix C). The relationship of the Keuka Lake watershed to the entire Oswego River Basin is indicated on the map (Appendix C) titled "Oswego River Basin - Basin Map." The irregular but somewhat rectangular shaped, north-south oriented watershed of some 182 square miles drains from the surrounding landscape directly into the Y-shaped, 20 mile long Keuka Lake. Numerous short, steep tributaries surrounded the lake with the larger tributaries; i.e., Sugar Creek, Glen Brook, Mitchellsville Creek, Softwater Creek, and Cold Brook which becomes Keuka Inlet, located within the west and southwest portions of the watershed. Keuka Lake itself has a surface area of some 18.3 square miles and a shoreline length of 55 miles. The surrounding terrain rises steeply to the hilltops which are at elevations 400 to 1200 feet above the Lake. Land use within the watershed is predominantly agricultural with large areas devoted to vineyards. Developed areas are located at Penn Yan, Keuka Park, Hammondsport, Branchport, and Pulteney. Additional runoff is diverted at times directly into Keuka Lake at a New York State Electric and Gas Corporation (NYSE&G) power station located at Keuka. This runoff occurs from a 45.5 square mile catchment area surrounding Waneta and Lamoka Lakes which lie within the Susquehanna River Basin. This diversion consists of a diversion canal 9000 feet long plus a 4400 feet long pipeline. The average diversion inflow rate is about 80 cfs or 158 acre-feet per day.

5.2 ANALYSIS CRITERIA

No hydrologic/hydraulic information was available regarding the original design for this dam. The 1960 Corps of Engineers report (Ref. 6) provided information regarding stage-storage data for Keuka Lake, and stage-discharge curves for the existing Birkett gate and the center masonry spillway. The stage-discharge curve calculated for the newer Rodney Hunt gates assumed fully open gates using both weir and orifice flow conditions for increasing water surface elevations.

The analysis of the spillway capacity of the dam was performed using the Corps of Engineers HEC-1 computer program, Dam Safety version. The computer modeling parameters for the drainage area were selected from the Oswego River Basin study (Ref. 7). The spillway design flood selected was the Probable Maximum Flood (PMF) in accordance with the Recommended Guidelines of the Corps of Engineers. The PMF storm event is that hypothetical flow resulting from the most critical combination of rainfall, minimum soil infiltration loss, and concentration of runoff at a specific location that is considered reasonably possible for a specific watershed.

5.3 SPILLWAY CAPACITY

The two Rodney Hunt gates, each 4.5 feet square, are the primary control structures and were analyzed for both weir and orifice flow conditions in the fully open position. The discharge coefficients, C, for weir and orifice flow respectively were 2.77 and 0.7.

Additional normal discharge capacity at the site is obtained from the Birkett gate which was also analyzed in a similar manner. This gate is normally positioned at a fixed opening; for the analysis, a fully open gate was used. Discharge coefficients of 2.77 and 0.42 respectively were determined using the existing stage-discharge curves. The center, masonry auxiliary spillway's discharge capacity was also obtained from the existing stage-discharge curve, developed using a weir coefficient of 3.1. Although there exists a 13 foot wide railroad underpass 55 feet right of the Rodney Hunt gates, any additional discharge capacity through this area was not considered.

Computed discharges for all site facilities are as follows (all gates fully open):

<u>ELEV. (USGS)</u>		<u>DISCHARGE (cfs)</u>
718.75	Top of Dam	1588
716.04	Auxiliary Spillway Crest	717

The flood analyses performed for this dam considered two conditions: the gates fully closed and fully open. From an initial water surface elevation of 714 (mid-summer stage), the spillways when fully open do not have sufficient capacity for discharging the peak outflow from one-half the PMF. For this storm event, the peak inflow is 51,947 cfs and the peak outflow is 2,884 cfs.

5.4 RESERVOIR CAPACITY

Normal lake levels fluctuate throughout the year between the elevations of 712 and 715. The available storage capacity for these elevations is 35,000 acre-feet which is equivalent to 3.6 inches of direct runoff from the watershed. Storage capacity to elevation 716 adds some 12,000 acre-feet (1.2 inches). Surge storage capacity to the top-of-dam elevation of 718.75 adds an additional 34,750 acre-feet (3.58 inches). The total storage capacity of Keuka Lake is 200,750 acre-feet for elevation 718.75. Since the dam is located approximately one mile downstream of the main body of Keuka Lake, stages recorded at the dam do not indicate corresponding lake levels. Gage readings have established the head losses along the outflow channel leading to the dam as being about 0.5 feet.

5.5 FLOODS OF RECORD

The maximum known flood in the watershed occurred on June 24, 1972 when a gage reading of 719.35 was recorded at Hammondsport. The watershed total precipitation during this 5 day event ranged from 8 to 10 inches of rain. In 1872, a higher lake level of 720.09 was recorded but the present structure did not exist as it does today for this storm event.

5.6 OVERTOPPING POTENTIAL

Records indicate that the present dam has been overtopped by approximately 0.5 feet during the maximum flood. No dam failure has been recorded. The analyses indicates the spillways do not have sufficient discharge capacity for one-half the PMF. The computed depth of overtopping is 1.84 feet for

this event. Overtopping would occur for all storm events exceeding 32% of the PMF.

5.7 EVALUATION

The spillway capacity is inadequate for the peak outflow from one-half the PMF. The Corps of Engineers report (Ref. 6) indicates discharges in excess of 500 cfs will cause damage in the channel downstream of the dam. Hence, dam failure would not significantly increase the hazard to loss of life downstream from that which would exist just prior to an overtopping-induced failure. Therefore, the spillway is assessed as inadequate.

SECTION 6: STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

Visual observations of the dam did not reveal any serious deficiencies which would affect the stability of the dam. There was a small amount of scour behind the upstream ends of the sheet piling and one of the concrete posts supporting the gate mechanism at the northern end of the dam was deteriorated. A small amount of leakage exiting at the base of the masonry wall was observed in a prior inspection. With the exception of these deficiencies, the dam appeared to be structurally in good condition

b. Design and Construction Data

Design and construction data was very limited. Plans for the southern portion of the dam which was reconstructed in 1966 were available and have been included in Appendix E. No accurate cross sections of the Birket Gate section or the auxiliary spillway section could be located. Due to this lack of cross sectional data, and due to the unique composition of this structure, no stability analysis was performed. However, there was no evidence of any stability problems on this structure.

SECTION 7: ASSESSMENT/RECOMMENDATION

7.1 ASSESSMENT

a. Safety

The Phase I inspection of the Keuka Lake Outlet Dam did not reveal conditions which constitute a hazard to human life or property. Minor deficiencies such as the deterioration of concrete on the northern slide gate control mechanism and the leakage exiting at the base of the wall could affect the safety of the dam if the conditions worsen.

The spillways, while not having sufficient discharge capacity for passing one-half the PMF, are considered to be inadequate. During periods of unusually heavy precipitation and high runoff occurring over the watershed, continuous surveillance should be provided both at the dam and in the downstream areas to warn residents of high floodwater conditions. Such surveillance procedures and other measures deemed necessary should be developed, documented and placed in readiness for future use as part of a detailed emergency operation-action plan. A warning system should also be developed and implemented; to be used in the event of dam failure.

b. Adequacy of Information

The information available for the preparation of this report was considered to be adequate for Phase I inspection purposes.

c. Urgency


The remedial measures outlined in the following section should be taken within 6 months of the date of final approval of this report.

7.2 RECOMMENDED MEASURES

1. Repair the concrete on the post supporting the northern slide gate control mechanism.
2. Fill the small scoured areas behind the sheet pile walls and protect this area with riprap.
3. Monitor the leakage in the masonry wall and if it becomes worse, take remedial actions.
4. Remove the debris which has accumulated in the vicinity of the northern spillway gates.
5. Cut trees and brush which line the channel in the vicinity of the dam.
6. Develop and implement a detailed emergency operation-action plan and warning system.

APPENDIX A


PHOTOGRAPHS



Entrance Channel to Southern Service Spillway
Note Erosion Behind End of Sheet Piling




Entrance Channel Looking Upstream-Note trees
Hanging Over Approach Channel



Southern Service Spillway-Rodney Hunt Gates




Southern Service Spillway-Looking Upstream




Northern Service Spillway-Birkett Gate



Channel Downstream of Birkett Gate




Control Mechanism For Birkett Gate



Deteriorated Concrete on One of Support Posts for Birkett Gate



Auxiliary Spillway Channel with Earth Fill on Upstream Slope



Masonry Wall on Auxiliary Spillway-Slight
Leakage Reported at Base of Wall



Northern Wall of Approach Channel
Note Gabions and Riprap



Railroad Bridge Upstream of Dam which
Restricts Flow

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam KEUKA LAKE OUTLET DAM
Fed. I.D. # NY-390 DEC Dam No. 53B-613
River Basin OSWEGO
Location: Town PENN YAN County YATES
Stream Name KEUKA LAKE OUTLET
Tributary of _____
Latitude (N) 42° 39.6' Longitude (W) 77° 3.2'
Type of Dam CONCRETE, MASONRY & EARTH FILL
Hazard Category C
Date(s) of Inspection 5/8/80
Weather Conditions OVERCAST 50°F
Reservoir Level at Time of Inspection 714

b. Inspection Personnel W. LYNICK R. WARRENDER

c. Persons Contacted (Including Address & Phone No.) _____
WESLEY RYDER - UTILITIES MANAGER - VILLAGE OF PENN YAN
315-536-3374

d. History:

Date Constructed 1900 Date(s) Reconstructed 1962
Designer _____ C. HOBAN
Constructed By _____
Owner VILLAGE OF PENN YAN

2) Embankment

a. Characteristics

- (1) Embankment Material EARTH & ROCK FILL
- (2) Cutoff Type _____
- (3) Impervious Core _____
- (4) Internal Drainage System _____
- (5) Miscellaneous _____

b. Crest NOT APPLICABLE

- (1) Vertical Alignment _____
- (2) Horizontal Alignment _____
- (3) Surface Cracks _____
- (4) Miscellaneous _____

c. Upstream Slope

- (1) Slope (Estimate) (V:H) FLAT
- (2) Undesirable Growth or Debris, Animal Burrows NONE
- (3) Sloughing, Subsidence or Depressions NO

(4) Slope Protection BANK RETAINER STONE WALL AT
UPSTREAM TOE

(5) Surface Cracks or Movement at Toe NONE

d. Downstream Slope

(1) Slope (Estimate - V:H) NOT APPLICABLE

(2) Undesirable Growth or Debris, Animal Burrows

(3) Sloughing, Subsidence or Depressions

(4) Surface Cracks or Movement at Toe

(5) Seepage

(6) External Drainage System (Ditches, Trenches; Blanket)

(7) Condition Around Outlet Structure

(8) Seepage Beyond Toe

e. Abutments - Embankment Contact

SATISFACTORY

(1) Erosion at Contact _____

(2) Seepage Along Contact _____

3) Drainage System

a. Description of System NONE

b. Condition of System _____

c. Discharge from Drainage System _____

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.) _____

STAFF GAGE ON UPSTREAM SHEET PILE IN FRONT
OF SERVICE SPILLWAY GATES

5) Reservoir

- a. Slopes KEUKA LAKE & OUTLET CHANNEL - BRUSH & TREES GROWING ALONG CHANNEL SHOULD BE CUT TO REDUCE DEBRIS PROBLEM
- b. Sedimentation _____
- c. Unusual Conditions Which Affect Dam NARROW CHANNEL TO DAM RAILROAD BRIDGE UPSTREAM COLLECTS DEBRIS & POUNDS SOME H₂O.

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) 6 HOMES; SEWAGE TREATMENT PLANT; SEVERAL LOCAL ROADS; INDUSTRIAL PLANT JUST BEYOND LEFT ABUTMENT
- b. Seepage, Unusual Growth NONE
- c. Evidence of Movement Beyond Toe of Dam NO
- d. Condition of Downstream Channel SATISFACTORY

7) Spillway(s) (Including Discharge Conveyance Channel)

- 2 GATES ON ~~EASTERN~~ ^{SOUTHERN} END; 1 SLIDE GATE ON NORTHERN END; AUXILIARY CHANNEL IN MIDDLE - GRASS SLOPE CONCRETE OVER MASONRY WALL
- a. General SOUTHERN GATES INSTALLED IN 1966 - 2 RODNEY HUNT GATE VALVES - SOME SCOUR IN ~~BACK~~ OF SHEET PILING ON UPSTREAM END
- b. Condition of Service Spillway NORTHERN END GATE - CONCRETE SPALLED AND REMOVED UNDER 1 CORNER OF SUPPORT. FURTHER REMOVAL WOULD MAKE GATE INOPERABLE
SOUTHERN END GATES - LIFT GATE MECHANISM WAS RECENTLY GREASED & IS OPERABLE - SOME DEBRIS CAUGHT IN OPENING

c. Condition of Auxiliary Spillway Good

d. Condition of Discharge Conveyance Channel

4 ARCHES UNDER MAIN STREET BRIDGE - COULD LIMIT
FLOW SOMEWHAT

8) Reservoir Drain/Outlet NONE - ALTHOUGH SERVICE SPILLWAY
CAN BE USED TO LOWER WATER LEVEL

Type: Pipe _____ Conduit _____ Other _____

Material: Concrete _____ Metal _____ Other _____

Size: _____ Length _____

Invert Elevations: Entrance _____ Exit _____

Physical Condition (Describe): _____ Unobservable _____

Material: _____

Joints: _____ Alignment _____

Structural Integrity: _____

Hydraulic Capability: _____

Means of Control: Gate _____ Valve _____ Uncontrolled _____

Operation: Operable _____ Inoperable _____ Other _____

Present Condition (Describe): _____

9) Structural

a. Concrete Surfaces BIRKETT GATE - FRONT GATE LIFT SUPPORT
BLOCKS CRACKED & BROKEN

~~ROONEY HUNT~~ ~~ROCKING~~ GATE - CONCRETE IS GOOD

b. Structural Cracking NONE - MASONRY SURFACES ALL
SATISFACTORY

c. Movement - Horizontal & Vertical Alignment (Settlement) OKAY

d. Junctions with Abutments or Embankments. SATISFACTORY

e. Drains - Foundation, Joint, Face NONE

f. Water Passages, Conduits, Sluices SATISFACTORY

g. Seepage or Leakage BACKWATER PREVENTED OBSERVATION

- h. Joints - Construction, etc. _____

- i. Foundation _____

- j. Abutments _____

- k. Control Gates GATE IN SATISFACTORY CONDITION EXCEPT CONCRETE
DETERIORATED ON ONE POST OF BIRKETT (NORTHERN) GATE

- l. Approach & Outlet Channels NORTHERN WALL GABIONS AND
RIP RAP - GOOD CONDITION

- m. Energy Dissipators (Plunge Pool, etc.) NONE

- n. Intake Structures _____

- o. Stability APPEARS TO BE SATISFACTORY

- p. Miscellaneous _____

APPENDIX C

HYDROLOGIC/HYDRAULIC
ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

KEUKA
LAKE
NY - 390

1

AREA-CAPACITY DATA:

(USGS)

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>718.75</u>	<u> </u>	<u>200,750</u>
2) Design High Water (Max. Design Pool)	<u>N/A</u>	<u> </u>	<u> </u>
3) Auxiliary Spillway Crest	<u>716.04</u>	<u> </u>	<u>166,000</u>
4) Pool Level with Flashboards	<u>N/A</u>	<u> </u>	<u> </u>
5) Service Spillway Crest (INVERTS)	RODNEY HUNT - 708.43 BIRKETT - 709	<u> </u>	80,500 <u>86,500</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>N/A</u>
2) Spillways @ Maximum High Water	<u>1588</u>
3) Spillway @ Design High Water	<u>N/A</u>
4) Spillways @ Auxiliary Spillway Crest Elevation	<u>717</u>
5) Low Level Outlet	<u>N/A</u>
6) Total (of all facilities) @ Maximum High Water	<u>1588</u>
7) Maximum Known Flood (ELEV. 719.35 ON LAKE ± 718.85 @ DAM)	<u>1600 ±</u>
8) At Time of Inspection [EL = 714.18 ±]	<u>473 ±</u>

CREST:

ELEVATION: 718.75Type: CONCRETE & MASONRYWidth: 5'Length: ~~85~~ ± 100'Spillover GATES { BIRKETT
RODNEY HUNT (2)AUXILIARY CHANNELLocation EACH ENDCENTER

SPILLWAY:

INVERT)	BIRKETT	SERVICE	RODNEY HUNT ⁽²⁾	AUXILIARY	
	709		708.43	Elevation	716.04
	GATE		GATE	Type	MASONRY; DROP STRUCTURE
	4'		4.5'	Width	3' 5.5 8'
				Type of Control	
	MANUAL HOIST		MANUAL HOIST	Uncontrolled	✓
				Controlled:	
	—		—	Type	N/A
				(Flashboards; gate)	
	1		2	Number	—
	4' x 5.4'		4.5' x 4.5'	Size/Length	50.8'
				Invert Material	MASONRY
				Anticipated Length of operating service	—
	N/A		N/A	Chute Length	N/A
	N/A		N/A	Height Between Spillway Crest & Approach Channel Invert (Weir Flow)	-0-

HYDROMETEROLOGICAL GAGES:

Type : UGGS RECORDER
WATER STAGE - LAKESTAFF @ DAMLocation: HAMMONDSPORTON SHEET PILE WALL

Records:

Date - 6/24/72Max. Reading - 719.35

FLOOD WATER CONTROL SYSTEM:

Warning System: NO

Method of Controlled Releases (mechanisms):

SERVICE SPILLWAYS (BIRKETT GATE & 2 RODNEY HUNT GATES)

DRAINAGE AREA: 182 SQ MILES 116,480 ACRES

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: AGRICULTURAL (VINEYARDS)

Terrain - Relief: MODERATE TO STEEP

Surface - Soil: TILLABLE - SLOW INFILTRATION

Runoff Potential (existing or planned extensive alterations to existing
(surface or subsurface conditions)

N/A

Potential Sedimentation problem areas (natural or man-made; present or future)

NO

Potential Backwater problem areas for levels at maximum storage capacity
including surcharge storage:

NONE, EXCEPT FOR THOSE STRUCTURES AROUND ENTIRE
PERIMETER OF LAKE

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the
Reservoir perimeter:

Location: NO

Elevation: _____

Reservoir:

Length @ Maximum Pool: 20± (Miles)

Length of Shoreline (@ Spillway Crest) 55± (Miles)

PROJECT GRID


JOB KEUKA LAKE		SHEET NO. 1/	CHECKED BY	DATE
SUBJECT WATERSHED PARAMETERS		COMPUTED BY WCL		DATE 6/17/80

DRAINAGE AREA — LAKE SURFACE AREA :		
(DA)	(LSA)	
181.44 SQ MI.	18.15 SQ MI.	PLANIMETERED
	(11620 ACRES) ←	
→ 182 SQ MI.	18.3 SQ MI.	USGS GAGE # 04232450 @ HAMMONDPORT
178.5 SQ MI.	17.5 SQ MI.	CORPS ENGINEERS RPT: KEUKA OUTLET - 6/1960
196 SQ MI.	18.3 SQ MI.	BULL. 68 - GAZETTEER

PMP - RAINFALL :

HMR # 33		HMR # 51		USE # 33
ON ZONE BOUNDARY (1 1/2")				
200 SQ MI - 24 HR = 22" (INDEX)		AREA (SQ MI)	WIRE	DEPTH
		10	6	24.5
(HRS) ZONE 1		ZONE 2		
AVE (INS)				
6	76	79	17.4	81
12	90	91	20	91
24	101	101	22.2	101
48	107	110	24.2	112
		5000	6	7.2
			12	10.1
			24	12.1
			48	14.4
			72	15.6
		1000	6	12
			12	14.8
			24	17
			48	19.5
			72	20.5

46 5810
K&E SEMI-LOGARITHMIC 3 CYCLES x 140 DIVISIONS
KLUFFEL & ISSER CO. MADE IN U.S.A.



PROJECT GRID

JOB KEUKA LAKE	SHEET NO. 3/	CHECKED BY	DATE
SUBJECT WATERSHED PARAMETERS		COMPUTED BY WCL	DATE 6/18/80
PMP - RAINFALL:			
HMR #51 PLOT OF D-A-D:			
FOR DA = 182 SQ MI.			
DURATION = 6 12 24 48 72			
DEPTH (INS) → 16.6 19.7 22 24.6 25.8			
(USING INDEX = 24 HREVENT) %: 75.5 89.5 100 111.8 117.3			
SNYDER SYNTHETIC UNIT HYDROGRAPH:			
DA = 182 SQ MI.			
LONGEST DRAINAGE PATH = L = 29.4 MI.			
DIST. TO CENTROID OF DA = L_{CA} = 14.6 MI.			
(USE) $C_t = 2.0$ SLOPES (MODERATE TO STEEP)			
LAG TIME = $t_p = C_t \left(L \times L_{CA} \right)^{0.3}$			
$t_p = 2 (29.4 \times 14.6)$			
$t_p = 12.32$ HRS			
UNIT RAINFALL DURATION = $t_r = \frac{t_p}{5.5}$			
$t_r = 2.24$ HRS			
(USE) $t_r = 2$			
ADJUSTED LAG TIME = $T_p = t_p + 0.25(t_r - t_r)$			
$T_p = 12.32 + 0.25(2 - 2.24)$			
$T_p = 12.26$ HRS			
PEAKING COEFF = $C_p = 0.625$			

PROJECT GRID

JOB KEUKA LAKE		SHEET NO. 4/	CHECKED BY	DATE
SUBJECT WATERSHED PARAMETERS		COMPUTED BY WCL		DATE 6/19/80


SOIL INFILTRATION (LOSS RATES):		
SOIL NAME:	SCS SOIL GROUP	LOSS (INS/HR)
(MAJOR)		
E4 - MARDIN	C	0.1
Ew2 (WET) - VOLUSIA	C	0.1
(MINOR)		
Aw1 (WET) - APPLETON	C	0.1
A3 - HONEOUE	B	0.2
DH1 (HILLY STEEP) - LORDSTOWN-MARDIN	C	0.1
H2 - HOWARD	B	0.2

REF: OSWEGO RIVER BASIN - STUDY:		
(INS/HR)		
LOSS	INITIAL = 1.50	} BASED UPON MODELING CALIBRATED TO JUNE 1972 EVENT (AGNES)
RATES	CONSTANT = 0.03	

BASE FLOW	STRTQ	= 100 cfs	} SAME ✓
	QRCN	= 800 cfs	
	RTIQR	= 1.6	

PROJECT GRID

JOB KEUKA LAKE		SHEET NO. 5/	CHECKED BY	DATE
SUBJECT STAGE - STORAGE DATA			COMPUTED BY WCL	DATE 6/19/80
CORPS ENGINEERS (6/19/80 REPORT)				
PLATE I - II : KEUKA OUTFLET				
ELEV.	AC-FT (X 1000)			
721.7	240			
721	230			
720	217			
718	191			
716	166			
714	142	-- [USE AS NORMAL POOL]		
712	119			
710	97			
708	76			



OSWEGO RIVER WATERSHED, NEW YORK

KEUKA LAKE OUTLET

PENN YAN, NEW YORK

STORAGE CAPACITY CURVE

KEUKA LAKE


U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY PROJECT REPORT (PUBLIC LAW 685)
DATED: JUNE 1960

PROJECT GRID

JOB KEUKA LAKE		SHEET NO. 6/	CHECKED BY	DATE
SUBJECT MASONRY SPILLWAY (CENTER) - DISCHARGE CAPACITY		COMPUTED BY WCL		DATE 6/20/80
SINGLE SPILLWAY @ 50.3' = CREST LENGTH (FIELD MEASURED)				
CORPS ENGINEERS (6/1960 RPT) - KEUKA OUTLET				
RATING CURVE USING $Q = CLH^{3/2}$: PLATE I-9 CREST @ 716.04 L = 50.8' C = 3.1				
WATER SURF ELEV. H Q				
716.04 — —				
(USE 716)				
716.5 0.5 55				
717 1 155				
717.5 1.5 285				
718 2 445				
718.5 2.5 620				
718.75 2.75 715				
719 3 815				

TOP
ABOUT

KEUKA LAKE OUTLET DAM



HEAD IN FEET
HEADWATER ELEV - DAM CREST ELEV.

NY - 390

NOTES

1. HEADWATER ELEVATION IS GAGE READING MINUS 0.36'
2. DAM CREST ELEVATION 716.04

OSWEGO RIVER WATERSHED, NEW YORK

KEUKA LAKE OUTLET

PENN YAN, NEW YORK

RATING CURVE

MAIN STREET DAM

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY PROJECT REPORT (PUBLIC LAW 665)
DATED: JUNE 1960

PROJECT GRID

JOB				SHEET NO.		CHECKED BY		DATE	
KEUKA LAKE				7/					
SUBJECT				DISCHARGE CAPACITY		COMPUTED BY		DATE	
RODNEY HUNT SLUICE GATES -						WCL		6/20/80	
TWIN 54" x 54" GATES — VARIABLE OPENING:									
(4.5' x 4.5')									
ORIFICE C ≈ 0.7 AREA = 20.25 SQ FT.									
INVERT = 708.43									
TOP OPENING = 712.93									
WEIR FLOW: $Q = CLH^{3/2}$									
ORIFICE FLOW: $Q = CA\sqrt{2gH}$									
CONDITION: GATE FULLY OPEN (MAX CAPACITY):									
WATER SURF ELEV H L = 4.5' C = 2.77 (SIMILAR TO BIRKETT GATE)									
Q 21Q									
INN. 708.43 — — —									
709 2.57 5.4 10.8									
710 11.57 24.5' 419									
712 3.57 34 163									
TOP 712.93 4.5 119 232									
713 4.57 123 244									
714 5.57 164 328									
714.4 5.97 182 364									
715 6.57 210 420									
→ 715.6 7.17 239 478									
ORIFICE $H = (H_0 - 2.25)$									
ASSUME SAME ELEV CAUSES L $Q = (0.7)(20.25)\sqrt{2gH}$									
ORIFICE FLOW TO OCCUR AT THESE GATES $Q = 113.75\sqrt{H}$									
H H Q 21Q									
716 7.57 5.32 262 524									
716.5 8.07 5.82 274 548									
717 8.57 6.32 296 572									
717.5 9.07 6.82 297 524									
718 9.57 7.32 307 614									
718.5 10.07 7.82 318 636									
— 718.75 10.32 8.07 323 646									
719 10.57 8.32 328 656									

RODNEY HUNT MACHINE CO.

ESTABLISHED 1840

ORANGE, MASSACHUSETTS, 01364, U.S.A.

TELEPHONE 617-844-2811 TWX 617-844-6142

August 18, 1966

State of New York
Conservation Department
Division of Water Resources
Central Regional Office
418 East State Street
Ithaca, New York

Attention: Mr. Frank J. Keller, P.E.
Senior Hydraulic Engineer

Subject: Keuka Lake Outlet Structure
Sluice Gate
Rodney Hunt Shop Order 63076-2

Gentlemen:

We have received your letter of July 11th but because of the preparation for vacations and the vacation we have not been able to answer it until now. We are sorry about this delay and hope that it has not seriously inconvenienced you.

You requested a discharge rating chart for the [REDACTED] which we furnished on this project through R. E. Clark & Sons. We do not have a rating chart as such on this but our experience and the available literature would seem to indicate that a coefficient of discharge of 0.70 is reasonable for these gates. We have seen figures from 0.65 to 0.75 used and for our calculation purposes, we normally use the 0.70 figure. We believe that a stage-discharge curve based on this coefficient will be accurate enough to allow you to set the opening of the gate accordingly. Finer settings may be determined by experience over the years.

We hope that this information will satisfactorily meet your requirements. If we can assist you further in any way on this, please let us know.

Very truly yours,

RODNEY HUNT COMPANY

R. W. Henderson

R. W. Henderson, Manager
Water Control Equipment Division

RWH/bg

DIVISIONS: WATER CONTROL EQUIPMENT • TEXTILE MACHINERY • INDUSTRIAL ROLLS


PROJECT GRID

JOB KEUKA LAKE		SHEET NO. 8/		CHECKED BY		DATE	
SUBJECT BIRKETT GATE - DISCHARGE CAPACITY				COMPUTED BY WCL		DATE 6/30/80	
SINGLE 4' x 5.4' GATE - NORMALLY @ FIXED OPENING: (48" x 64.8")							
ORIFICE				AREA = 311.6 SQ FT			
INVERT = 709.0				(FIELD)			
TOP OPENING = 714.4				TOP OF CONC @ GATE = 719.1 (MEASURED)			
CORPS ENGINEERS (6/19/60 RPT) - KEUKA OUTLET							
RATING CURVES FOR WEIR & ORIFICE FLOW: PLATES I-7 & I-8							
CONDITION: GATE FULLY OPEN (MAX CAPACITY):							
WATER SURF. ELEV.		H	Q	RECALCULATE "C": $C = \frac{Q}{LH^{3/2}}$			
INV.	709			L = 4'		NO TAILWATER	
	710	1	11	←		SL 715	
	712	3	58			SL 719	
	712.93	3.913	86				
	713	4	89			SL 719	
	714	5	124			SL 717	
TOP	714.4	5.4	139			SL 717	
	715	6	163			SL 717	
	715.6	6.6	188	←		SL 717	
	716	7	193	←		C.42 (1.537)	
	716.5	7.5	199				
	717	8	206			C.42 (1.516)	
	717.5	8.5	212			C.42 (1.501)	
	718	9	218			C.419 (1.491)	
	718.75	9.75	227	←		C.419 (1.491)	
	719	10	230				
	718.5	9.5	224	↗		C.419 (1.491)	
				CR = CE FLOW: $C = \frac{Q}{A\sqrt{H}}$			
				A = 311.6			

H TO
CENTER OF
ORIFICE

KEUKA LAKE OUTLET DAM

NY - 392



KEUKA LAKE OUTLET DAM


NY-390

NOTES

- 1 HEADWATER ELEVATION IS GAGE READING MINUS 0.3'
- 2 TAILWATER FROM CURVE DATED 20 OCTOBER 1959
- 3 ORIFICE CONSIDERED UNSUBMERGED UNTIL TAILWATER IS ABOVE TOP OF OPENING

OSWEGO RIVER WATERSHED, NEW YORK
 KEUKA LAKE OUTLET
 PENN YAN, NEW YORK
 RATING CURVE - ORIFICE FLOW
 BIRKETT GATE
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY PROJECT REPORT (PUBLIC LAW 685)
 DATED: JUNE 1960

HEAD IN FEET
 H FOR UNSUBMERGED = HEADWATER - (SILL + $\frac{1}{2}$ GATE OPENING)
 H FOR SUBMERGED = HEADWATER - TAILWATER



PROJECT GRID

JOB KEUKA LAKE		SHEET NO. 9/		CHECKED BY		DATE	
SUBJECT DISCHARGE CAPACITY - NON-OVERFLOW SECTIONS (FLOOD CONDITION)		COMPUTED BY WCL		DATE 6/20/80			
RR UNDERPASS - 60' RT OF SPILLWAY:							
BROAD-CRESTED WEIR : $Q = CLH^{3/2}$							
L = 13' C = 2.63							
CREST ELEV = 718.3							
ELEV.	H	Q					
718.3	—	—					
718.5	0.2	3					
718.75	0.45	10.3					
719	0.7	30					
BIRKETT GATE :							
PLATFORM (OVERTOP)				MASONRY WALLS BETWEEN GATE & CENTER SPILLWAY			
$Q = CLH^{3/2}$				$Q = CLH^{3/2}$			
C = 3.1				C = 3.1			
L = 15.8'				L = 29.9'			
CREST = 718.8				CREST = 718.8			
Q	H	ELEV.	H	Q			
—	—	718.8	—	—			
4	0.2	719	0.2	8			
RODNEY HUNT GATE :							
MASONRY WALLS BETWEEN GATE & CENTER SPILLWAY							
$Q = CLH^{3/2}$							
C = 3.1 L = 14.5' CREST = 718.8							
Q	H	ELEV.					
—	—	718.8					
4	0.2	719					

PROJECT GRID

JOB		SHEET NO.		CHECKED BY		DATE	
SUBJECT		COMPUTED BY		DATE			
KEUKA LAKE		10/					
STAGE - DISCHARGE : SUMMARY		WCL		6/23/80			
STAGE (ELEV)	CENTER MAZONRY SPILLWAY	R-H GATES (2) (FULLY-OPEN)	BIRKETT GATE (FULLY-OPEN)	RR UNDERPASS	NON- OVERFLOW SECTIONS(3)	(cfs) TOTAL	
708.43						—	
709		10.8				10.8	
710		49	11			60	
712		168	58			226	
713		244	89			333	
714		328	124			452	
715		420	163			583	
715.6		478	188			666	
716		524	193			717	
716.5	55	548	199			802	
717	155	572	206			933	
717.5	285	594	212			1091	
718	445	614	218			1277	
718.5	620	636	224	3		1483	
718.75	715	646	227	10		1598	
719	815	656	230	20	16	1737	

USE AS
NORMAL
POOL

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 26 FEB 79
MODIFIED FOR HONEYWELL APR 79

NEW YORK STATE
DEPT OF ENVIRONMENTAL CONSERVATION
FLOOD PROTECTION BUREAU

RUN DATE 06/25/80 KEUKA LAKE DAM NY-390
VILLAGE OF PENN VAN OSWEGO RIVER BASIN
VATES COUNTY
SNYDER UH

NO NHR NMN IDAY IHR IMIN METRC IPLT IPRT NSTAN
200 2 0 0 0 0 0 0 0 0
JOPER 5 NWT LROPT TRACE
0 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NRTIO= 2 LRTIO= 1
RTIOS= 0.50 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH
ISIAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
SUBBSH 0 0 0 0 0 0 0 0 0

HYDROGRAPH DATA
IHYDG IUHG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
1 1 182.00 0. 182.00 0. 0. 0 0 1 0

PRECIP DATA
SPFE PMS R6 R12 R24 R48 R72 R96
0. 22.00 79.00 91.00 101.00 110.00 0. 0.

TRSPC COMPUTED BY THE PROGRAM IS 0.880

LOSS DATA
LROPT STRKR DLTGR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
0 0. 0. 1.00 0. 0. 1.00 1.50 0.03 0. 0.10

UNIT HYDROGRAPH DATA
TP= 12.26 CP=0.63 NTA= 0

RECESSION DATA
SRTIO= 100.00 GRCSN= 800.00 RTIOR= 1.60
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 7.00 AND R= 5.50 INTERVALS

UNIT HYDROGRAPH 33 END-OF-PERIOD ORIGINATES, LAG= 12.14 HOURS, CP= 0.63 VOL= 1.00
373. 1367. 2706. 4149. 5352. 6028. 6082. 5443. 4535. 3779.
3149. 2624. 2186. 1822. 1518. 1265. 1054. 878. 732. 610.
508. 423. 294. 245. 204. 170. 142. 118. 98.
82. 62. 57.

END-OF-PERIOD FLOW
MO.OA HR.MI PERIOD RAIN EXCS LOSS COMP Q MO.OA HR.MN PERIOD RAIN EXCS LOSS COMP G
1.01 2.00 1 0.02 0.00 0.02 96. 1.09 10.00 101 0. 0. 0. 80.
1.01 4.00 2 0.02 0.00 0.02 95. 1.09 12.00 102 0. 0. 0. 76.

1.01	8.00	0.07	0.00	0.02	0.01	0.02	0.01	1.09	14.00	103	0.	0.	0.	13.
1.01	8.00	0.07	0.01	0.06	0.01	0.06	0.01	1.09	16.00	104	0.	0.	0.	69.
1.01	10.00	0.07	0.01	0.06	0.01	0.06	0.01	1.09	18.00	105	0.	0.	0.	66.
1.01	12.00	0.07	0.01	0.06	0.01	0.06	0.01	1.09	20.00	106	0.	0.	0.	63.
1.01	14.00	0.35	0.04	0.32	0.04	0.32	0.04	1.09	22.00	107	0.	0.	0.	60.
1.01	16.00	0.72	0.07	0.65	0.07	0.65	0.07	1.10	0.	108	0.	0.	0.	57.
1.01	18.00	0.29	0.13	0.16	0.13	0.16	0.13	1.10	2.00	109	0.	0.	0.	55.
1.01	20.00	0.03	0.00	0.03	0.00	0.03	0.00	1.10	4.00	110	0.	0.	0.	52.
1.01	22.00	0.03	0.00	0.03	0.00	0.03	0.00	1.10	6.00	111	0.	0.	0.	50.
1.02	0.	0.03	0.00	0.03	0.00	0.03	0.00	1.10	8.00	112	0.	0.	0.	48.
1.02	2.00	0.26	0.20	0.05	0.20	0.05	0.05	1.10	10.00	113	0.	0.	0.	45.
1.02	4.00	0.26	0.20	0.05	0.20	0.05	0.05	1.10	12.00	114	0.	0.	0.	43.
1.02	6.00	0.26	0.20	0.05	0.20	0.05	0.05	1.10	14.00	115	0.	0.	0.	41.
1.02	8.00	0.77	0.72	0.05	0.72	0.05	0.05	1.10	16.00	116	0.	0.	0.	39.
1.02	10.00	0.77	0.72	0.05	0.72	0.05	0.05	1.10	18.00	117	0.	0.	0.	38.
1.02	12.00	0.77	0.72	0.05	0.72	0.05	0.05	1.10	20.00	118	0.	0.	0.	36.
1.02	14.00	3.98	3.92	0.05	3.92	0.05	0.05	1.10	22.00	119	0.	0.	0.	34.
1.02	16.00	8.11	8.06	0.05	8.06	0.05	0.05	1.11	0.	120	0.	0.	0.	33.
1.02	18.00	3.21	3.16	0.05	3.16	0.05	0.05	1.11	2.00	121	0.	0.	0.	31.
1.02	20.00	0.39	0.33	0.05	0.33	0.05	0.05	1.11	4.00	122	0.	0.	0.	30.
1.02	22.00	0.39	0.33	0.05	0.33	0.05	0.05	1.11	6.00	123	0.	0.	0.	28.
1.03	0.	0.39	0.33	0.05	0.33	0.05	0.05	1.11	8.00	124	0.	0.	0.	27.
1.03	2.00	0.	0.	0.	0.	0.	0.	1.11	10.00	125	0.	0.	0.	26.
1.03	4.00	0.	0.	0.	0.	0.	0.	1.11	12.00	126	0.	0.	0.	25.
1.03	6.00	0.	0.	0.	0.	0.	0.	1.11	14.00	127	0.	0.	0.	24.
1.03	8.00	0.	0.	0.	0.	0.	0.	1.11	16.00	128	0.	0.	0.	22.
1.03	10.00	0.	0.	0.	0.	0.	0.	1.11	18.00	129	0.	0.	0.	21.
1.03	12.00	0.	0.	0.	0.	0.	0.	1.11	20.00	130	0.	0.	0.	20.
1.03	14.00	0.	0.	0.	0.	0.	0.	1.11	22.00	131	0.	0.	0.	19.
1.03	16.00	0.	0.	0.	0.	0.	0.	1.12	0.	132	0.	0.	0.	18.
1.03	18.00	0.	0.	0.	0.	0.	0.	1.12	2.00	133	0.	0.	0.	17.
1.03	20.00	0.	0.	0.	0.	0.	0.	1.12	4.00	134	0.	0.	0.	16.
1.03	22.00	0.	0.	0.	0.	0.	0.	1.12	6.00	135	0.	0.	0.	15.
1.04	0.	0.	0.	0.	0.	0.	0.	1.12	8.00	136	0.	0.	0.	14.
1.04	2.00	0.	0.	0.	0.	0.	0.	1.12	10.00	137	0.	0.	0.	13.
1.04	4.00	0.	0.	0.	0.	0.	0.	1.12	12.00	138	0.	0.	0.	12.
1.04	6.00	0.	0.	0.	0.	0.	0.	1.12	14.00	139	0.	0.	0.	11.
1.04	8.00	0.	0.	0.	0.	0.	0.	1.12	16.00	140	0.	0.	0.	11.
1.04	10.00	0.	0.	0.	0.	0.	0.	1.12	18.00	141	0.	0.	0.	10.
1.04	12.00	0.	0.	0.	0.	0.	0.	1.12	20.00	142	0.	0.	0.	9.
1.04	14.00	0.	0.	0.	0.	0.	0.	1.12	22.00	143	0.	0.	0.	8.
1.04	16.00	0.	0.	0.	0.	0.	0.	1.13	0.	144	0.	0.	0.	8.
1.04	18.00	0.	0.	0.	0.	0.	0.	1.13	2.00	145	0.	0.	0.	7.
1.04	20.00	0.	0.	0.	0.	0.	0.	1.13	4.00	146	0.	0.	0.	7.
1.04	22.00	0.	0.	0.	0.	0.	0.	1.13	6.00	147	0.	0.	0.	6.
1.05	0.	0.	0.	0.	0.	0.	0.	1.13	8.00	148	0.	0.	0.	6.
1.05	2.00	0.	0.	0.	0.	0.	0.	1.13	10.00	149	0.	0.	0.	5.
1.05	4.00	0.	0.	0.	0.	0.	0.	1.13	12.00	150	0.	0.	0.	5.
1.05	6.00	0.	0.	0.	0.	0.	0.	1.13	14.00	151	0.	0.	0.	5.
1.05	8.00	0.	0.	0.	0.	0.	0.	1.13	16.00	152	0.	0.	0.	4.
1.05	10.00	0.	0.	0.	0.	0.	0.	1.13	18.00	153	0.	0.	0.	4.
1.05	12.00	0.	0.	0.	0.	0.	0.	1.13	20.00	154	0.	0.	0.	4.
1.05	14.00	0.	0.	0.	0.	0.	0.	1.13	22.00	155	0.	0.	0.	4.
1.05	16.00	0.	0.	0.	0.	0.	0.	1.14	0.	156	0.	0.	0.	4.
1.05	18.00	0.	0.	0.	0.	0.	0.	1.14	2.00	157	0.	0.	0.	3.
1.05	20.00	0.	0.	0.	0.	0.	0.	1.14	4.00	158	0.	0.	0.	
1.05	22.00	0.	0.	0.	0.	0.	0.	1.14	6.00	159	0.	0.	0.	
1.06	0.	0.	0.	0.	0.	0.	0.	1.14	8.00	160	0.	0.	0.	
1.06	2.00	0.	0.	0.	0.	0.	0.	1.14	10.00	161	0.	0.	0.	
1.06	4.00	0.	0.	0.	0.	0.	0.	1.14	12.00	162	0.	0.	0.	
1.06	6.00	0.	0.	0.	0.	0.	0.	1.14	14.00	163	0.	0.	0.	
1.06	8.00	0.	0.	0.	0.	0.	0.	1.14	16.00	164	0.	0.	0.	
1.06	10.00	0.	0.	0.	0.	0.	0.	1.14	18.00	165	0.	0.	0.	
1.06	12.00	0.	0.	0.	0.	0.	0.	1.14	20.00	166	0.	0.	0.	
1.06	14.00	0.	0.	0.	0.	0.	0.	1.14	22.00	167	0.	0.	0.	
1.06	16.00	0.	0.	0.	0.	0.	0.	1.15	0.	168	0.	0.	0.	
1.06	18.00	0.	0.	0.	0.	0.	0.							
1.06	20.00	0.	0.	0.	0.	0.	0.							
1.06	22.00	0.	0.	0.	0.	0.	0.							
1.06	24.00	0.	0.	0.	0.	0.	0.							
1.06	26.00	0.	0.	0.	0.	0.	0.							
1.06	28.00	0.	0.	0.	0.	0.	0.							
1.06	30.00	0.	0.	0.	0.	0.	0.							
1.06	32.00	0.	0.	0.	0.	0.	0.							
1.06	34.00	0.	0.	0.	0.	0.	0.							
1.06	36.00	0.	0.	0.	0.	0.	0.							
1.06	38.00	0.	0.	0.	0.	0.	0.							
1.06	40.00	0.	0.	0.	0.	0.	0.							
1.06	42.00	0.	0.	0.	0.	0.	0.							
1.06	44.00	0.	0.	0.	0.	0.	0.							
1.06	46.00	0.	0.	0.	0.	0.	0.							
1.06	48.00	0.	0.	0.	0.	0.	0.							
1.06	50.00	0.	0.	0.	0.	0.	0.							
1.06	52.00	0.	0.	0.	0.	0.	0.							
1.06	54.00	0.	0.	0.	0.	0.	0.							
1.06	56.00	0.	0.	0.	0.	0.	0.							
1.06	58.00	0.	0.	0.	0.	0.	0.							
1.06	60.00	0.	0.	0.	0.	0.	0.							
1.06	62.00	0.	0.	0.	0.	0.	0.							
1.06	64.00	0.	0.	0.	0.	0.	0.							
1.06	66.00	0.	0.	0.	0.	0.	0.							
1.06	68.00	0.	0.	0.	0.	0.	0.							
1.06	70.00	0.	0.	0.	0.	0.	0.							
1.06	72.00	0.	0.	0.	0.	0.	0.							
1.06	74.00	0.	0.	0.	0.	0.	0.							
1.06	76.00	0.	0.	0.	0.	0.	0.							
1.06	78.00	0.	0.	0.	0.	0.	0.							
1.06	80.00	0.	0.	0.	0.	0.	0.							
1.06	82.00	0.	0.	0.	0.	0.	0.							
1.06	84.00	0.	0.	0.	0.	0.	0.							
1.06	86.00	0.	0.	0.	0.	0.	0.							
1.06	88.00	0.	0.	0.	0.	0.	0.							
1.06	90.00	0.	0.	0.	0.	0.	0.							
1.06	92.00	0.	0.	0.	0.	0.	0.							
1.06	94.00	0.	0.	0.	0.	0.	0.							
1.06	96.00	0.	0.	0.	0.	0.	0.							
1.06	98.00	0.	0.	0.	0.	0.	0.							
1.06	100.00	0.	0.	0.	0.	0.	0.							
1.06	102.00	0.	0.	0.	0.	0.	0.							
1.06	104.00	0.	0.	0.	0.	0.	0.							
1.06	106.00	0.	0.	0.	0.	0.	0.							
1.06	108.00	0.	0.	0.	0.	0.	0.							
1.06	110.00	0.	0.	0.	0.	0.	0.							
1.06	112.00	0.	0.	0.	0.	0.	0.							
1.06	114.00	0.	0.	0.	0.	0.	0.							
1.06	116.00	0.	0.	0.	0.	0.	0.							
1.06	118.00	0.	0.	0.	0.	0.	0.							
1.06	120.00	0.	0.	0.	0.	0.	0.							
1.06	122.00	0.	0.	0.	0.	0.	0.							
1.06	124.00	0.	0.	0.	0.	0.	0.							
1.06	126.00	0.												

[illegible]

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	103893.	100648.	72142.	30904.	1138800.
CMS	2942.	2850.	2043.	875.	32247.
INCHES		5.14	14.75	18.95	19.40
MM		130.67	374.63	481.44	492.81
AC-FT		49908.	143092.	183889.	188231.
THOUS CU M		61561.	176501.	226823.	232180.

[illegible]

CFS
 CMS
 INCHES
 AC-FT
 THOUS CU M

PEAK
 51947.
 1471.

6-HOUR
 50324.
 1425.
 2.57
 65.33
 24954.
 30780.

24-HOUR
 36071.
 1021.
 7.37
 187.31
 71546.
 88250.

72-HOUR
 15452.
 438.
 9.48
 240.72
 91944.
 113412.

TOTAL VOLUME
 569400.
 16124.
 9.70
 246.41
 94116.
 116090.

HYDROGRAPH AT STASUBSN FOR PLAN 1, RTIO 2

96.	97.	104.	119.	142.	182.	269.	452.	734.
1049.	1608.	1947.	2422.	3279.	4873.	7324.	11754.	21424.
37846.	78940.	95214.	103893.	103319.	94251.	81231.	68689.	57715.
48218.	33481.	27900.	23249.	19374.	16145.	13454.	11212.	9342.
7783.	5401.	4502.	3752.	3118.	2590.	2150.	1758.	1432.
1160.	762.	727.	693.	661.	631.	602.	574.	548.
523.	476.	454.	433.	413.	394.	376.	359.	343.
327.	297.	284.	271.	258.	247.	235.	224.	214.
204.	186.	177.	169.	161.	154.	147.	140.	134.
128.	116.	111.	106.	101.	96.	92.	88.	84.
80.	73.	69.	66.	63.	60.	57.	55.	52.
50.	45.	41.	41.	39.	38.	36.	34.	33.
31.	28.	27.	26.	25.	24.	22.	21.	20.
19.	18.	17.	16.	15.	15.	14.	13.	13.
12.	11.	11.	10.	10.	9.	9.	8.	8.
8.	7.	7.	6.	6.	6.	5.	5.	5.
5.	4.	4.	4.	4.	4.	3.	3.	3.
3.	3.	3.	2.	2.	2.	2.	2.	2.
2.	2.	2.	2.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.

CFS
 CMS
 INCHES
 AC-FT
 THOUS CU M

PEAK
 103893.
 2942.

6-HOUR
 100648.
 2850.
 5.14
 130.67
 49908.
 61561.

24-HOUR
 72142.
 2043.
 14.75
 374.63
 143092.
 176501.

72-HOUR
 30904.
 875.
 18.95
 481.44
 183889.
 226823.

TOTAL VOLUME
 1138800.
 32247.
 19.40
 492.81
 188231.
 232180.

HYDROGRAPH ROUTING

ROUTED HYDROGRAPH AT DAM - CENTER SPILLWAY AND ALL GATES		JPLT		JPRT		INAME		ISTAGE		IAUTO	
ISTAG	ICOMP	IECON	ITAPE	0	2	0	1	0	0	0	0
DAM	1	0	0	0	0	0	1	0	0	0	0
ROUTING DATA											
QLOSS	CLOSS	AVG	IRCS	ISAME	IOPT	IPMP	LSTR				
0.	0.	0.	1	1	0	0	0				
NSTPS NSTDL LAG AMSKK X TSK STORA ISPRAT											
1	0	0	0	0	0	0	-714.				
STAGE	708.43	713.99	714.00	715.00	715.60	716.00	716.50	717.00	717.50	718.00	
	718.50	718.75	719.00								
FLOW	0.	452.00	1701.00	583.00	666.00	717.00	802.00	933.00	1091.00	1277.00	
	1480.00	1588.00									
CAPACITY	76000.	97000.	119000.	142000.	166000.	191000.	217000.	230000.	240000.		
ELEVATION	708.	710.	712.	714.	716.	718.	720.	721.	722		

CREL SPWID CQGW EXPW ELEV COQL CAHEA EXPL
714.0 0. 0. 0. 0. 0. 0.

DAM DATA
TOPEL CQGD EXPD DAMWID
710.8 3.1 1.5 60.

STATION DAM, PLAN 1, RATIO 1

END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW									
	22.	34.	40.	45.	50.	57.	68.	88.	130.
	315.	452.	453.	453.	454.	456.	459.	464.	471.
	511.	554.	617.	696.	800.	984.	1203.	1419.	1616.
	2047.	2228.	2381.	2507.	2609.	2691.	2754.	2802.	2837.
	2876.	2883.	2884.	2880.	2871.	2859.	2844.	2827.	2808.
	2765.	2741.	2717.	2693.	2670.	2646.	2623.	2599.	2576.
	2531.	2508.	2486.	2464.	2442.	2420.	2399.	2378.	2357.
	2315.	2295.	2275.	2255.	2235.	2216.	2196.	2177.	2159.
	2122.	2103.	2086.	2068.	2050.	2033.	2016.	1999.	1983.
	1950.	1934.	1918.	1903.	1887.	1872.	1857.	1843.	1828.
	1800.	1786.	1773.	1759.	1746.	1733.	1720.	1708.	1695.
	1671.	1659.	1648.	1637.	1626.	1615.	1605.	1595.	1586.
	1569.	1560.	1552.	1543.	1535.	1526.	1518.	1510.	1502.
	1485.	1477.	1470.	1462.	1455.	1447.	1440.	1433.	1425.
	1411.	1404.	1396.	1389.	1382.	1375.	1368.	1361.	1354.
	1340.	1333.	1326.	1319.	1313.	1306.	1299.	1293.	1286.
	1273.	1267.	1261.	1254.	1248.	1242.	1236.	1230.	1224.
	1212.	1206.	1200.	1194.	1188.	1183.	1177.	1171.	1165.
	1154.	1148.	1143.	1137.	1131.	1126.	1120.	1115.	1109.
	1099.	1093.	1088.	1084.	1079.	1075.	1070.	1066.	1061.

STORAGE									
	141891.	141894.	141895.	141896.	141898.	141899.	141902.	141907.	141918.
	141965.	142000.	142047.	142119.	142225.	142385.	142646.	143074.	143785.
	147444.	151333.	156911.	163999.	172103.	180518.	188500.	195535.	201479.
	210473.	213773.	216436.	218568.	220258.	221581.	222597.	223360.	223912.
	224522.	224635.	224649.	224582.	224449.	224260.	224025.	223753.	223449.
	222768.	222395.	222009.	221623.	221239.	220856.	220475.	220094.	219715.
	218588.	218216.	217845.	217476.	217109.	216744.	216382.	216021.	215662.
	214951.	214598.	214248.	213900.	213554.	213210.	212868.	212529.	212192.
	211857.	211524.	211194.	210866.	210540.	210216.	209894.	209575.	209259.
	208630.	208319.	208011.	207704.	207400.	207098.	206798.	206499.	206204.
	205618.	205328.	205040.	204754.	204470.	204188.	203907.	203629.	203352.
	202805.	202533.	202264.	201996.	201730.	201465.	201202.	200941.	200681.
	200165.	199909.	199654.	199401.	199148.	198897.	198648.	198399.	198152.
	197662.	197419.	197177.	196936.	196696.	196457.	196220.	195984.	195749.
	195282.	195051.	194820.	194591.	194363.	194136.	193910.	193685.	193461.
	193017.	192797.	192578.	192360.	192143.	191927.	191712.	191498.	191286.
	190864.	190654.	190446.	190239.	190033.	189828.	189623.	189420.	189218.
	188816.	188617.	188418.	188221.	188024.	187829.	187634.	187440.	187248.
	186865.	186675.	186486.	186298.	186110.	185924.	185739.	185554.	185370.
	185006.	184825.	184645.	184465.	184287.	184109.	183932.	183755.	183579.

STAGE									
	714.0	714.0	714.0	714.0	714.0	714.0	714.0	714.0	714.0
	714.0	714.0	714.0	714.0	714.0	714.0	714.0	714.0	714.0
	714.5	714.8	715.2	715.8	716.5	717.2	717.8	718.3	718.8
	719.5	719.8	720.0	720.1	720.3	720.4	720.5	720.5	720.5
	720.6	720.6	720.6	720.6	720.6	720.6	720.5	720.5	720.5
	720.4	720.4	720.4	720.4	720.3	720.3	720.3	720.2	720.2
	720.1	720.1	720.1	720.1	720.0	720.0	720.0	719.9	719.9
	719.9	719.8	719.8	719.8	719.8	719.7	719.7	719.7	719.6
	719.6	719.6	719.6	719.5	719.5	719.5	719.5	719.4	719.4

PEAK OUTFLOW IS 2884. AT TIME 86.00 HOURS										
	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME					
719.1	2884.	2882.	2852.	2671.	318232.	719.1	719.0	719.0	719.0	719.1
718.9	82.	82.	81.	76.	9011.	718.9	718.8	718.8	718.8	718.9
718.7		0.15	0.58	1.61	5.42	718.7	718.6	718.6	718.6	718.7
718.5		3.74	14.81	41.61	137.71	718.5	718.4	718.4	718.4	718.5
718.3		1429.	5657.	15895.	52600.	718.3	718.3	718.2	718.4	718.3
718.1		1763.	6978.	19606.	64881.	718.1	718.1	718.2	718.4	718.3
718.0						718.0	718.0	718.0	718.2	718.2
717.8						717.8	717.9	717.9	718.0	718.0
717.7						717.7	717.8	717.9	717.9	717.8
717.5						717.5	717.6	717.6	717.7	717.7
							717.5	717.4	717.5	717.5
										717.4

OVN

STATION DAM, PLAN 1, RATIO 2
END-OF-PERIOD HYDROGRAPH ORIGINATES

		OUTFLOW		STORAGE		STAGE	
		100.	114.	136.	177.	260.	416.
44.	68.	90.	114.	136.	177.	260.	416.
453.	454.	458.	466.	472.	482.	499.	528.
580.	670.	1159.	2596.	3600.	4517.	5339.	6046.
6640.	7128.	7832.	8073.	8254.	8474.	8527.	8551.
8551.	8532.	8496.	8387.	8319.	8163.	8079.	7990.
7899.	7806.	7711.	7618.	7525.	7344.	7167.	7081.
6995.	6911.	6745.	6664.	6584.	6427.	6350.	6274.
6199.	6126.	5981.	5910.	5841.	5704.	5637.	5571.
5506.	5442.	5317.	5255.	5195.	5076.	5018.	4961.
4904.	4849.	4740.	4687.	4634.	4532.	4481.	4432.
4383.	4335.	4287.	4194.	4148.	4059.	4016.	3973.
3930.	3888.	3806.	3766.	3727.	3649.	3611.	3574.
3537.	3501.	3430.	3395.	3360.	3293.	3260.	3227.
3192.	3157.	3090.	3057.	3024.	2961.	2930.	2899.
2869.	2839.	2780.	2752.	2724.	2669.	2642.	2615.
2589.	2563.	2513.	2488.	2464.	2416.	2393.	2370.
2347.	2325.	2281.	2260.	2239.	2198.	2178.	2158.
2138.	2119.	2081.	2063.	2045.	2009.	1992.	1975.
1958.	1941.	1909.	1893.	1878.	1847.	1832.	1818.
1803.	1789.	1761.	1748.	1734.	1709.	1696.	1684.
		STORAGE		STAGE			
		141910.	141914.	141920.	141930.	141951.	141991.
141907.	141902.	141908.	141910.	141914.	141930.	141951.	141991.
142066.	142189.	142575.	143255.	143851.	144780.	146276.	148933.
153740.	161590.	187047.	220037.	235953.	249685.	261260.	270766.
278472.	284640.	293321.	298407.	299967.	301020.	301653.	301941.
301942.	301709.	300702.	299180.	298283.	297319.	296300.	295236.
294137.	293000.	289703.	288445.	287330.	286225.	285131.	284046.
282971.	281906.	279807.	277747.	276732.	275727.	274732.	273747.
272771.	271805.	269903.	268966.	268039.	267121.	266212.	265313.
263542.	262670.	260953.	259272.	258444.	257626.	256815.	256013.
255219.	254434.	252887.	251373.	250628.	249890.	249160.	248437.
247723.	247015.	245622.	244936.	244257.	243585.	242920.	242262.
240966.	240328.	239071.	238452.	237840.	237233.	236633.	236039.
234291.	234291.	233155.	232595.	232041.	231493.	230949.	230411.
229357.	228839.	227819.	227316.	226819.	226326.	225839.	225356.
224105.	223937.	223014.	222559.	222109.	221663.	221222.	220785.
219924.	219499.	218663.	218251.	217843.	217438.	216641.	216249.
215860.	215474.	214714.	214340.	213969.	213601.	213237.	212876.
212163.	211812.	210776.	210437.	210101.	209768.	209437.	209110.
208785.	208463.	207827.	207513.	207202.	206893.	206587.	206283.
205687.	205386.	204799.	204509.	204222.	203936.	203653.	203372.
		STAGE					
		714.0	714.0	714.0	714.0	714.0	714.0
714.0	714.0	714.0	714.0	714.0	714.0	714.0	714.0
714.0	714.0	714.0	714.1	714.2	714.2	714.4	714.6
715.0	715.0	717.7	718.9	720.2	721.4	722.4	723.9
724.4	724.6	725.4	725.6	725.8	725.9	726.0	726.6
726.0	726.0	725.9	725.9	725.8	725.8	725.6	725.6
725.5	725.5	725.2	725.2	725.1	725.0	724.9	724.8
724.7	724.6	724.5	724.4	724.3	724.2	724.1	724.1
724.0	723.9	723.8	723.7	723.6	723.5	723.4	723.4
723.3	723.3	723.2	723.1	723.0	722.9	722.9	722.8
722.8	722.7	722.6	722.5	722.4	722.3	722.3	722.3
722.2	722.2	722.1	722.0	722.0	721.9	721.9	721.8

721.0	720.9	720.9	720.8	720.7	720.6	720.6
720.6	720.5	720.5	720.4	720.4	720.3	720.3
720.2	720.2	720.2	720.1	720.0	720.0	719.9
719.9	719.9	719.9	719.8	719.7	719.7	719.7
719.6	719.6	719.6	719.5	719.5	719.4	719.4
719.4	719.3	719.3	719.3	719.2	719.2	719.2
719.1	719.1	719.1	719.0	719.0	719.0	718.9

PEAK OUTFLOW IS 8551. AT TIME 82.00 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
8551.	8544.	8427.	7725.	768743.
242.	242.	239.	219.	21768.
CFS	0.44	1.72	4.74	13.10
CMS	11.09	43.76	120.34	332.67
INCHES	4237.	16714.	45965.	127065.
MM	5226.	20617.	56698.	156732.
AC-FT				
THOUS CU M				

Page and 186 at Temp

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	RATIOS APPLIED TO FLOWS	
			PLAN RATIO	RATIO
			0.50	1.00
HYDROGRAPH AT	SUBBSN	182.00 (0.00)	1	51947. 103893.
			(1470.97)	(2941.93)
ROUTED TO	OAH	182.00 (0.00)	1	2884. 8551.
			(61.67)	(242.15)

11

PLAN 1

**ELEVATION
STORAGE
OUTFLOW**

INITIAL VALUE
713.99
141885.
0.

SPILLWAY CREST
714.00
142000.
452.

TOP OF DAM
716.75
200750.
1586.

RATIO	
OF	
PMF	
0.53	
1.00	

MAXIMUM
RESERVOIR
W.S.ELEV
720.59
726.04

MAXIMUM
DEPTH
OVER DAM
1.84
7.29

MAXIMUM
STORAGE
AC-FY
224649.
301942.

MAXIMUM
OUTFLOW
CF8
2884
8551

DURATION
OVER TQP
HOURS
180.00
352.00

TIME OF
MAX OUTFLOW
HOURS
06.00
02.00

TIME OF
FAILURE
HOURS
0.
0.

 FLOOD HYDROGRAPH PACK (HEC-1)
 LA SAFETY VERSION JULY 1978
 LAST MODIFICATION 20 FEB 79
 MODIFIED FOR HUP-EYFLL PR 79

 NEW YORK STATE
 DEPT. OF ENVIRONMENTAL CONSERVATION
 FLOOD PROTECTION BUREAU

 CSNAGO RIVER BASIN
 YATES COUNTY
 SNYDER LH
 0 0 0 0

NY-390
 VILLAGE OF PLIN J VAN

1 1.5 0.03 0.1

INFLOW HYDROGRAPH

ROUTED HYDROGRAPH AT DAM - CENTER SPILLWAY ONLY

1	A	KEUKA LAKE DAM	2	0	0	0	0	0
2	A		3	0	0	0	0	0
3	A		4	200	5			
4	0		5	01				
5	J	1	2	1				
6	J1	0.5	1					
7	K	C	SUBBSN					
8	K2							
9	M	1	182					
10	P	C	22	79	91	101	110	
11	T							
12	M	12.26	0.625					
13		100	800	1.6				
14		1	0AM					
15	K1							
16	Y							
17	Y1	1						
18	Y4	714	716	716.5	717	717.5	718	718.5
19	Y5	0	0	55	155	285	445	620
20	\$5	76000	97000	119000	142000	166000	191000	217000
21	\$F	708	710	712	714	716	718	720
22	\$S	716						
23	\$D	718.75	3.1	1.5	60.2			
24	K	99						
25	A							
26	A							
27	A							
28	A							
29	A							
30	A							

PEAK FLOW AND STORAGE (CONT. OF PE LUG.) SUMMARY FLOODMULTIPLE PLAN-RATIO ECCENTRIC COMPUTATIONS
 FLOWS (IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND))
 AREA IN SQUARE FEET (SQUARE METERETERS)

RATIOS APPLIED TO FLOWS

LOCATION	STATION	AREA	PLAN	RATIO 1	RATIO 2
				1.51	1.10
HYDROGRAPH AT	SURBSN	162.00 (0.00)	1	51.47, (1470.97)	103893, (2961.91)
ADJUSTED TO	DAM	162.00 (0.00)	1	2147, (60.81)	7633, (216.33)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION
STAG,
OUTFL.INITIAL VALUE
714.00
142000,
0.SPILLWAY CREST
716.00
146000,
0.TOP OF DAM
718.75
200750,
715.CENTER
SPILLWAY
ONLYPATIC
CF
PRF
0.50
1.00MAXIMUM
RESERVOIR
W.S. ELEV
720.82
720.33MAXIMUM
DEPTH
OVER DAM
2.13
7.58MAXIMUM
STORAGE
AC-FT
221444.
304104.MAXIMUM
OUTFLOW
CFS
2147.
7638.CLRATION
EVER TCP
FOURS
320.00
352.00TIME OF
MAX OUTFLOW
HOURS
98.00
92.00TIME OF
FAILURE
HOURS
0.
0.

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIO	1	RATIO	2	RATIOS APPLIED TO FLOWS									
								RATIO	3	RATIO	4	RATIO	5	RATIO	6	RATIO	7
HYDROGRAPH AT	SUBBSN	182.00 (5541.69)	1	31168. (882.58)	32207. (912.00)	0.31	0.32	0.32	0.33	0.34	0.35	0.36	0.37	0.38	0.39	0.40	0.41
ROUTED TO	DAM	182.00 (5541.69)	1	572. (16.19)	618. (17.49)	667. (18.89)	717. (20.30)	778. (22.02)	845. (23.92)	918. (25.92)	995. (28.02)	1078. (30.18)	1165. (32.40)	1258. (34.68)	1355. (37.02)	1458. (39.42)	1565. (41.88)

CENTER
SPILLWAY
ONLY

SUMMARY OF DAM SAFETY ANALYSIS

PLAN i

ELEVATION
STORAGE
OUTFLOW

INITIAL	VALUE
713.99	
141885.	
0.	

SPILLWAY CREST
716.00
16600.0

TOP OF DAM
718.75
260750.
715.

RATIC	CF	PMF
	0.30	
	0.31	
	0.32	
	0.33	
	0.34	
	0.35	
	0.50	

MAXIMUM
RESERVOIR
W.S. ELEV
718.36
718.49
718.62
718.75
718.88
719.01
720.87

MAXIMUM
DEPTH
OVER DAM
0.
0.
0.
0.00
0.13
0.26
2.12


MAXIMUM	
STORAGE	
AC-FY.	
195710.	
197411.	
199111.	
200809.	
202488.	
204156.	
228347.	

MAXIMUM	572.
OUTFLCH	618.
CFS	667.
	717.
	770.
	845.
	2141.

CLERICAL EVER TCP HOURS	
0.	
0.	
0.	
10.00	
60.00	
92.00	
320.00	

TIME OF	
MAX OUTFLOW	
HOURS	
98.00	
96.00	
96.00	
96.00	
96.00	
94.00	
88.00	

[illegible]




OSWEGO RIVER BASIN

BASIN MAP

U.S. ARMY ENGINEER DISTRICT, BUFFALO

LAKE ONTARIO

KEUKA
LAKE
WATERSHED



STREAMS TRIBUTARY TO LAKE ONTARIO

04232450 KEUKA INLET (KEUKA LAKE) AT HAMMONDSPORT, NY
(Formerly published as Keuka Lake at Hammondsport)

LOCATION.--Lat 42°24'22", long 77°13'08", Steuben County, Hydrologic Unit 04140201, on left bank of Keuka Inlet at end of Liberty Street extension at Hammondsport; and 300 ft (91 m) upstream from mouth.

DRAINAGE AREA.--Keuka Inlet 25.0 mi² (64.8 km²); Keuka Lake at mouth 182 mi² (471 km²).

PERIOD OF RECORD.--August 1960 to current year.

REVISED RECORDS.--WSP 2112: Drainage area. WRD NY 1974: 1973.

GAGE.--Water-stage recorder. Datum of gage is National Geodetic Vertical Datum of 1929. Prior to October 1, 1975, at datum 710.00 ft (216.408 m) higher.

REMARKS.--Lake regulated by village of Penn Yan; prior to July 1962, by New York State Electric and Gas Corp. Area of water surface, 18.3 mi² (47.4 km²). During each year, a large part of flow from 45.5 mi² (118 km²) of drainage area of Mud Creek (Susquehanna River basin) is diverted into Keuka Lake for power development. For table of diversion, see station 01528700.

EXTREMES FOR PERIOD OF RECORD.--Maximum elevation, 719.35 ft (219.258 m) June 24, 1972; minimum daily, 711.40 ft (216.835 m) Feb. 2, 3, 1961.

EXTREMES FOR CURRENT YEAR.--Maximum elevation, 715.15 ft (217.978 m) March 11; minimum, 712.65 ft (217.216 m) Feb. 18.

ELEVATION, IN FEET NGVD, WATER YEAR OCTOBER 1978 TO SEPTEMBER 1979
MEAN VALUES

DAY	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1	713.08	713.18	713.21	712.86	713.51	712.87	714.50	714.24	714.42	714.40	714.55	713.77
2	713.11	713.15	713.19	713.26	713.40	712.90	714.48	714.20	714.42	714.40	714.61	713.76
3	713.07	713.15	713.16	713.33	713.25	712.98	714.50	714.16	714.42	714.41	714.65	713.82
4	713.06	713.15	713.16	713.34	713.20	713.16	714.44	714.10	714.41	714.40	714.58	713.82
5	713.07	713.14	713.16	713.35	713.15	713.53	714.47	714.06	714.41	714.39	714.49	713.81
6	713.03	713.15	713.13	713.36	713.10	714.69	714.41	714.02	714.42	714.36	714.45	714.13
7	713.03	713.17	713.10	713.35	713.10	714.92	714.42	713.98	714.41	714.35	714.32	714.23
8	713.03	713.17	713.09	713.38	713.10	715.02	714.40	713.97	714.42	714.34	714.25	714.18
9	713.01	713.16	713.15	713.35	713.10	715.04	714.43	713.97	714.49	714.32	714.19	714.09
10	712.98	713.18	713.13	713.37	713.05	715.08	714.57	713.98	714.49	714.31	714.10	714.00
11	712.99	713.19	713.10	713.30	713.00	715.10	714.67	714.00	714.51	714.30	714.07	713.95
12	712.99	713.22	713.07	713.20	712.90	715.07	714.75	714.00	714.53	714.32	713.99	713.88
13	713.07	713.19	713.03	713.10	712.85	715.03	714.73	714.01	714.50	714.32	713.91	713.79
14	713.19	713.18	713.00	713.05	712.85	715.02	714.79	714.02	714.48	714.32	713.86	713.79
15	713.20	713.20	712.97	713.00	712.80	715.01	714.80	714.03	714.46	714.33	713.85	713.84
16	713.21	713.21	712.95	713.00	712.75	714.97	714.80	714.05	714.45	714.39	713.85	713.78
17	713.19	713.20	712.93	713.00	712.70	714.92	714.79	714.07	714.45	714.41	713.80	713.72
18	713.16	713.23	712.93	713.00	712.65	714.89	714.78	714.08	714.45	714.40	713.80	713.65
19	713.17	713.24	712.90	713.05	712.70	714.85	714.75	714.07	714.43	714.38	713.80	713.62
20	713.18	713.26	712.87	713.05	712.75	714.80	714.71	714.07	714.40	714.37	713.79	713.52
21	713.16	713.26	712.88	713.10	712.80	714.77	714.68	714.08	714.35	714.36	713.79	713.47
22	713.16	713.25	712.95	713.20	712.90	714.74	714.65	714.11	714.36	714.34	713.77	713.46
23	713.17	713.23	712.84	713.30	713.00	714.71	714.61	714.10	714.40	714.34	713.74	713.38
24	713.17	713.25	712.81	713.37	712.92	714.69	714.56	714.16	714.38	714.39	713.74	713.31
25	713.15	713.26	712.90	713.29	712.36	714.70	714.50	714.23	714.37	714.40	713.75	713.29
26	713.15	713.26	712.88	713.47	712.85	714.68	714.45	714.24	714.33	714.40	713.75	713.28
27	713.20	713.25	712.85	713.51	712.86	714.64	714.42	714.26	714.29	714.42	713.81	713.28
28	713.19	713.27	712.83	713.53	712.86	714.58	714.39	714.29	714.33	714.40	713.81	713.31
29	713.20	713.26	712.80	713.52	---	714.55	714.35	714.32	714.34	714.41	713.79	713.35
30	713.18	713.24	712.76	713.52	---	714.55	714.29	714.37	714.35	714.39	713.80	713.36
31	713.16	---	712.74	713.51	---	714.53	---	714.40	---	714.39	713.80	---
MEAN	713.12	713.21	712.98	713.26	712.96	714.55	714.57	714.12	714.42	714.37	714.01	713.69
MAX	713.21	713.27	713.21	713.53	713.51	715.10	714.80	714.40	714.53	714.42	714.65	714.23
MIN	712.98	713.14	712.74	712.86	712.65	712.87	714.29	713.97	714.29	714.30	713.74	713.28

CAL YR 1978 MEAN 714.04 MAX 716.26 MIN 712.74
WTR YR 1979 MEAN 713.78 MAX 715.10 MIN 712.65

249

LOCATION.--Lat 42°29'06", long 77°06'39", Steuben County, Hydrologic Unit 02050105, at entrance to conduit on Diversion Canal, 0.8 mi (1.3 km) east of Keuka, and 1.0 mi (1.6 km) north of Wayne.

PERIOD OF RECORD.--October 1966 to current year.

REMARKS.--Records for January 1951 to September 1966 on file. Sketch indicates diversion from Mamoka-Waneta Lakes (Susquehanna River Basin) to Keuka Lake (Oswego River Basin).

COOPERATION.--Records furnished by New York State
Electric and Gas Corp.

EXTREMES FOR PERIOD OF RECORD.--Maximum discharge, 73 ft³/s (2.07 m³/s) June 23, 1972; no flow for many days each year.

EXTREMES FOR CURRENT YEAR.--Maximum discharge, 66 ft³/s
(1.87 m³/s) Oct. 11, 12; no flow many days.





Figure 8.--Gaging stations and transbasin diversion, Cohocton River-Keuka Lake area.

DISCHARGE, IN CUBIC FEET PER SECOND, WATER YEAR OCTOBER 1978 TO SEPTEMBER 1979
MEAN VALUES

DAY	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1	.00	.00	31	.00	.00	.00	.00	.00	26	.00	.00	.00
2	.00	.00	31	23	.00	.00	.00	.00	.00	.00	.00	.00
3	.00	.00	31	48	.00	.00	.00	.00	.00	32	.00	.00
4	.00	.00	31	55	.00	.00	.00	.00	.00	36	.00	.00
5	.00	.00	.00	55	.00	.00	.00	.00	.00	.00	.00	.00
6	.00	32	20	55	.00	.00	.00	.00	.00	.00	.00	.00
7	.00	55	33	55	.00	.00	.00	.00	.00	.00	.00	.00
8	.00	55	33	23	.00	.00	.00	.00	.00	.00	.00	.00
9	.00	55	32	.00	.00	.00	.00	5.2	.00	.00	.00	.00
10	33	55	.00	.00	.00	.00	.00	14	.00	.00	.00	.00
11	66	55	19	.00	.00	.00	.00	8.0	.00	.00	.00	.00
12	66	55	33	.00	.00	.00	.00	.00	.00	.00	.00	.00
13	51	55	33	.00	.00	.00	.00	.00	.00	.00	.00	.00
14	46	48	33	.00	.00	.00	.00	24	.00	.00	.00	.00
15	46	42	34	.00	.00	.00	.00	49	.00	.00	.00	.00
16	27	42	34	.00	.00	.00	.00	55	.00	.00	.00	.00
17	.00	37	34	.00	.00	.00	.00	55	.00	15	.00	.00
18	.00	37	34	.00	.00	.00	.00	35	.00	.00	.00	.00
19	.00	37	34	.00	.00	.00	.00	.00	.00	.00	.00	.00
20	.00	35	33	.00	.00	.00	.00	.00	.00	.00	.00	.00
21	.00	35	33	.00	.00	.00	.00	31	.00	.00	.00	.00
22	.00	16	34	.00	.00	.00	.00	55	.00	.00	.00	.00
23	.00	.00	34	.00	.00	.00	.00	55	.00	.00	.00	.00
24	.00	.00	34	.00	.00	.00	.00	55	.00	.00	.00	.00
25	.00	.00	34	.00	.00	.00	.00	28	.00	.00	.00	.00
26	.00	.00	34	.00	.00	.00	.00	.00	.00	.00	.00	32
27	.00	18	34	.00	.00	.00	.00	.00	.00	.00	.00	49
28	.00	34	34	.00	.00	.00	.00	.00	.00	.00	.00	55
29	.00	34	34	.00	.00	.00	.00	24	.00	.00	.00	55
30	.00	34	34	.00	.00	.00	.00	42	.00	.00	.00	55
31	.00	.00	34	.00	.00	.00	.00	42	.00	.00	.00	.00
TOTAL	335.00	866.00	936.00	314.00	.00	.00	.00	577.20	25.00	83.00	.00	246.00
MEAN	10.8	28.9	30.2	10.1	.000	.000	.000	18.6	.87	2.68	.000	8.20
MAX	66	55	34	55	.000	.000	.000	55	26	36	.00	55
MIN	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00	.00
CAL YR 1978	TOTAL	10772.00	MEAN	29.5	MAX	68	MIN	.00				
WTR YR 1979	TOTAL	3383.20	MEAN	9.27	MAX	66	MIN	.00				

KEUKA LAKE OUTLET DAM

NY-390



NOTES

1. GAGE EXTENDS OVER RANGE OF 0 TO 3.33 FEET ELEVATION OF ZERO OF GAGE IS 708.0 USC & GS DATUM
2. * INCLUDES JACOB'S BROOK FLOW
3. * DISCHARGE FROM GATES
4. CURVE PREPARED 20 OCTOBER 1959

OSWEGO RIVER WATERSHED, NEW YORK

KEUKA LAKE OUTLET

PENN YAN, NEW YORK


TAILWATER RATING CURVE

MAIN STREET DAM

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY PROJECT REPORT (PUBLIC LAW 683)

DATED, JUNE 1960



Source - OWNER

47 2613

K-E 1 YEAR 10 DAY 10 MIN DIVISION

KEUKA LAKE DAM

NY-390

#53B-613 OSWEGO

This afternoon the new dam gates were put into operation. These new gates are located in a brick and steel wall across the south channel. ~~Each gate opening is 54" wide and 54" high over which is fitted a cast iron gate lifted by a worm gear and cap screw mechanism. Thus these gates can be opened from the bottom any desired amount up to the top of the opening. The capacity for flow is exactly the same as for the old gates and is based upon the height setting of each gate and the pressure created by the lake level. For the present each gate is about 12" open which will permit moderate flow. Very soon they will be opened fully to permit maximum runoff during the spring rise period. At the same time, the gate in the north channel which is now restricted in flow by the conduit under the construction work access will be fully opened too.~~

In summary, the gates in the north and south channel are now both in good condition and will be operated to maintain spring fillup. The target level for June 1st is slightly above 714.0 to be maintained as nearly as possible thereafter until mid-September.

March 2nd, 1966
JT Andrews/hst

Best Available Copy

APPENDIX D
REFERENCES

APPENDIX D



REFERENCES

- 1) M.G. Cline and R.L. Marshall, General Soil Map of New York State, Cornell University Agriculture Experiment Station, March 1977.
- 2) P. Greenson and F. Robison, Characteristics of New York Lakes-Gazetteer, Part 1, Bulletin 68, US Geological Survey, 1970.

Y.W. Isachsen and W.G. McKendree, Brittle Structures Map of New York State, New York State Museum, 1977.
- 4) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition, McGraw-Hill, 1963.
- 5) University of the State of New York, Geology of New York, Education Leaflet 20, Reprinted 1973.

U.S. Army; Corps of Engineers; Buffalo District:
- 6) Keuka Outlet at Penn Yan, New York, Detailed Project Report for Flood Control, June 1960.
- 7) Oswego River Basin, Water Resources Management Study, Preliminary Feasibility Report Appendices, May 1978.
- 8) U.S. Department of Commerce; Weather Bureau;
Hydrometeorological Report No. 33:
Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 square miles and durations of 6, 12, 24, and 48 hours; April 1956.
- 9) U.S. Department of Commerce; NOAA:
Hydrometeorological Report No. 51:
Probable Maximum Precipitation Estimates, United States East of the 105th Meridian; June 1978.
- 10) U.S. Geological Survey; Water Resources Data for New York - Water Year 1979, Water Data Report NY-79-1, Volume 1, May 1980.

APPENDIX E
DRAWINGS



MAJOR FLOOD CONTROL PROJECT
KEUKA OUTLET AT PEUN YAN, NEW YORK

GENERAL MAPS

SCALE AS SHOWN


U. S. ARMY ENGINEER DISTRICT, BUFFALO

AN ADJUTANT GENERAL'S PROJECT REPORT


WATER

KEUKA LAKE OUTLET
DAM

NY - 390




MAY - 1980



PLAN OF CONTROL STRUCTURE AREA

KEUKA LAKE DAM
NY-390




SECTION A-A

KEUKA LAKE OUTLET
 PENN YAN , NEW YORK
 MAIN STREET DAM AND
 CONTROL GATES

MAY - 1980

KEUKA LAKE DAM
 NY-390




WALL SECTION
NO SCALE

KEY 3' DEEP X 4" WIDE

COPPER WATER STOP

BAY 11 LOG





Best Available Copy


PLAN
HANDRAIL NOT SHOWN
NO SCALE

3


FACE OF FOOTING



REMOVE 8" EXISTING BRIDGE RAIL. PLACE NEW
2 RAIL 1 1/4" PIPE RAILING FROM NORTH END OF
EXISTING RAIL TO SOUTH END LANDING. PROVIDE
PROTECTIVE BARRIER ACROSS OPENING DURING
CONSTRUCTION.



STAIRWAY
PLAN
SCALE: 1/2 IN = 1 FT





The technical drawings illustrate the dimensions and components of a grate assembly. The side view on the left shows a cross-section of the grate with a hatched pattern, indicating a recessed area. Key dimensions and labels include:

- 3" CLEAR**: Indicated on the left side of the grate.
- 3" CLEAR**: Indicated on the right side of the grate.
- GRATING RECESS**: Labeled on the right side of the grate.

The top view on the right shows the plan of the grate assembly. Key dimensions and labels include:

- 3'-0"**: Indicated for the width of the grate.
- 3'-0"**: Indicated for the length of the grate.
- RETICUL GRATE**: Labeled on the right side of the grate.

ELEV. 708.38

OVERLAP
40 N

HANDRAIL


ELEV.
712.93

ELEV. 708.43


EXISTING
MASONRY
WALL

D



SECTION




PLAN
 LOWER LANDING
 FLOOR PLATE NOT SHOWN
 SCALE 1/4" = 1'-0"




9





SECTION A-A
SCALE 1 IN. = 1 FT.




14 RISERS
7 1/2
13 TREADS
10




SECTION B-B
SCALE 1 IN. = 1 FT.






REINFORCING PLAN
SCALE: 1/4" = 1'-0"



SECTION OF
NORTH CHANNEL
FACING NORTH
NO SCALE

11
COPPER WATER STOP KEY 3 DEE




PROPOSED
GATE INSTALLATION
NO SCALE

NEW GATES IN
PLACE OF ANDREW
GATE

ELEV. 708.38

6' WIDE

PLAN
LOWER LANDING
FLOOR PLATE NOT SHOWN
SCALE 1/4" = 1'-0"




STAIR CONNECTION
TO LANDING SAME
AS SECTION B-B

PLAN UPPER L
FLOOR PLATE NOT
SCALE 1/4" = 1'-0"

IS IN
DREWS

N
NDING
NOT SHOWN
IN 11"



12 C 20.7

6x6x1/4" L
6" LONG

3x3x1/2" L
BACK TO BACK

WELD ALL CONNECTIONS

4x4x
6-8" L
DRILL FOR
4018

PLAN FOR THE
RECONSTRUCTION OF GATES AND STRUCTURE
ON THE SOUTH BRANCH OF KEUKA LAKE
AT MAIN STREET BRIDGE IN
PENN YAN, NEW YORK

SCALE: AS SHOWN SHEET 2 OF 2
NOVEMBER 18, 1965 REVISED

Owen C. Hoban

NYS LIC. # 115 800

UPPER LANDING
PLATE NOT SHOWN
SCALE: 1/4" = 1'-0"

12 C 20.7
6x6x1/4 L
6" LONG

EXIST. S.W.

3x3x1/4 Ls
BACK TO BACK

WELD ALL CONNECTIONS

4x4x1/4 L
6' 8" LONG
DRILL FOR 1" BOLTS
48" SPACING

PLAN FOR THE


RECONSTRUCTION OF GATES AND STRUCTURES
UPPER BRANCH OF KEUKA LAKE, OUTLET
OUT MAIN STREET BRIDGE IN
PENN YAN, NEW YORK

SCALE AS SHOWN SHEET 2 OF 2
NOVEMBER 18, 1965 REVISED NOV 22, 1965

NYS LIC RE LS 8900



NO 390

OSWEGO




LOCATION PLAN

THIS



LAST NO.
 SECTION A-A
 SCALE 1/4"

ST. 11



9 718.04

PRC EL 7090

IN. A-A

577

99

ACE-2

1966-1967

EARTH-FILL 24

DATA 1.3
ETC.
S.A.S.

Phyllanthus

— 100 —

C

54

I

7 -

ML. H. DG

JO. JO. E
1941-1942

F. C. S.


1941-1942

1941-1942


8

71

1




EXISTING
SECTION B-B
SCALE 1/2"=5'




EXISTING
SECTION C-C
SCALE 1/2"=5'


9



237
RING
ON B-3
SCALE 1/5




237
ON C-3
SCALE 1/5



PLAN
SHOWN

10



9015

17

PROCEEDING

NY
C-1
EE 105

0+4 0+56 0+57.9 DATUM 108

PLAN FOR THE
RECONSTRUCTION OF GATES AND STRUCTURES
ON THE SOUTH BRANCH OF KEUKA LAKE OUTLET
AT MAIN STREET BRIDGE IN
PENN YAN, NEW YORK

SCALE AS SHOWN—SHEET 1 OF 2

NOVEMBER 18, 1965 REVISED NOV. 22, 1965

Owen C. Hoban N.Y.S. LIC. PE & LS #9603

NY-390

OSWEGO

13